

APPROVED SCHEDULE - B

BBMP/E-PMT/21/2017-18, Date: 15.02.2018


Improvements of roads and drains at Balaji layout and surroundings at Kodigehalli ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				N N Sreenivasaiah	
				In Figures	In Words
1	350.4	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3 (P.No.142, I.No.19.1 of PW, P&IWD SR 2016-17)	Cum	174.0	Rupees One Hundred Seventy Four Only
2	94.095	Removing & Refixing Stone slabs of drains and Pointing in C.M(1:3) (P.No.25, I.No.5.33 of PW, P&IWD SR 2016-17)	Sqm	75.0	Rupees Seventy Five Only
3	16.6	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete. 7.5cms thick (P.No.25, I.No.5.31.1 of PW, P&IWD SR 2016-17)	Sqm	621.0	Rupees Six Hundred Twenty One Only
4	51.14	KSRRB 4-1.2: Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.2 of PW, P&IWD SR 2016-17)	Cum	4990.0	Rupees Four Thousand Nine Hundred Ninety Only
5	112.5	Providing laying plain / reinforced cement concrete for Box Drain walls of thickness 10cm to 20 cm including centering shuttering form work etc. complete as per approved drawing and design MORTH Specification No. 1500,1700,2200 PCC M 20 Grade upto 0.75 m height using concrete mixture. (P.No.265., I.No.37.59.2 PW, P&IWD SR 2016-17)	Cum	10293.0	Rupees Ten Thousand Two Hundred Ninety Three Only
6	6.19	KSRRB - 4.9.2: Providing TMT steel reinforcement Fe500 for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. (P.No.17, I.No.4.46.2 of PW, P&IWD SR 2016-17)	MT	59939.0	Rupees Fifty Nine Thousand Nine Hundred Thirty Nine Only
7	32.8	KSRRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not less than 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 conforming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 (P.No.25, I.No.5.26.2 of PW, P&IWD SR 2016-17)	sqm	897.0	Rupees Eight Hundred Ninety Seven Only
8	1.85	KSRRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.6 of PW, P&IWD S.R 2016-17)	Cum	5381.0	Rupees Five Thousand Three Hundred Eighty One Only
9	343.8	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	1711.0	Rupees One Thousand Seven Hundred Eleven Only

Signature of the contractor

Signature of the Executive Engineer
Executive Engineer

S.No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				N N Sreenivasaiah	
				In Figures	In Words
10	5.73	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No.4.6 of PW,P&IWTD S.R 2016-17)	Cum	5381.0	Rupees Five Thousand Three Hundred Eighty One Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
